BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/06/2013-14, Date:05.11.2013 **ITEM NO:63**

SCHEDULE-B

NAME OF WORK: Improvements & Asphalting to Nrupatunga road & Krishne gowda Layout Main & cross road in Dasarahalli ward No 15

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **R MANGALARAJU**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	557.28	90.72	Rupees Ninety and Seventy Two Paise Only
2	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	4145	2.59	Rupees Two and Fifty Nine Paise Only
3	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam Specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per Specifications.	Cum	19.35	1121.04	Rupees One Thousand One Hundred Twenty One and Four Paise Only
4	Providing, laying and rolling with vibratory roller of built-up spray grout layer over prepared base consisting of a two layer composite construction of compacted crushed coarse aggregates using motor grader for aggregates. Key stone chips spreader may be used with application of bituminous binder after each layer, and with key aggregates placed on top of the second layer to serve as a base confirming to the line, grades and cross-section specified, the compacted layer thickness being 75mm Complete as per specifications.	Sqm	414.5	268.92	Rupees Two Hundred Sixty Eight and Ninety Two Paise Only
5	Providing and applying tack coat on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (Excluding cleaning of road surface) including cost of all Materials, labour, HOM of machineries complete as per specifications.	Sqm	4145	21.71	Rupees Twenty One and Seventy One Paise Only

Signature of the Contractor

Executive Engine

6	Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause No. 500.8 complete in all respects as per specifications. With 80/100 grade bitumen using 40-60 HMP using Mechanical paver complete as per specifications.	Cum	122.98	9794.52	Rupees Nine Thousand Seven Hundred Ninety Four and Fifty Two Paise Only
7	Carriage of Mixed Materials complete as per specifications.	Cum	122.98	52.11	Rupees Fifty Two and Eleven Paise Only
8	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and lying of hot applied Thermoplastic Compound 2.5mm thick including Reflectrising Glass Beads at 250 gms per Sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications.	m	154.8	471.96	Rupees Four Hundred Seventy One and Ninety Six Paise Only
9	Providing & fixing pre cast solid concrete Kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete of size 450x20x400 mm complete as per specifications.	No	1112	316.44	Rupees Three Hundred Sixteen and Forty Four Paise Only
10	Providing and applying floor painting with ready mix two coats (Excluding priming coat) on new s concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.	Sqm	722.8	44.28	Rupees Forty Four and Twenty Eight Paise Only
11	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specifications.	Cum	557.28	78.0	Rupees Seventy Eight Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,